STUDENT PROJECTS LABORATORY - LOCKOUT / TAGOUT [LOTO] PROCEDURE

ENERGY ISOLATION SPECIFICATION | ASSET: FAB-02 | TAG: G0767-01

Grizzly G0767 4"x79" Tube & Pipe Notcher

Authorized LOTO Personnel: Sr. Instructional Lab Supervisor (Max Wright) & Student Research Assistants (SRAs)

Notification Channel: Max Wright - Teams / Text Message | Zone: Zone 5: Fabrication, Sheet Metal & Abrasive Finishing (FAB)

STEP 1 - NORMAL MACHINE SHUTDOWN PROCEDURE

Push large red paddle OFF button (Left side).

STEP 2 - HAZARDOUS ENERGY SOURCES, MAGNITUDES & ISOLATION POINTS

Source #1: Electrical (120V AC)

Isolation Location: Ceiling drop cord.

Lockout Procedure: Unplug ceiling drop cord and apply Rotating Electrical Plug Lockout; depress green start button to verify zero energy.

STEP 3 - STORED / RESIDUAL ENERGY DISSIPATION

Wait for 2 HP motor and 5,900 FPM abrasive belt to coast to a complete stop.

STEP 4 - ZERO-ENERGY VERIFICATION ('TRY' STEP)

Depress green start button on G0767 Notcher to verify zero energy.